

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)

Tajuk Projek : KERJA MEMBAIKPULIH, MENAIKTARAF SERTA KERJA -KERJA YANG BERKAITAN DI BANGUNAN BLOK A UNTUK UNIVERSITI TEKNOLOGI MARA DI UiTM KAMPUS JALAN OTHMAN, PETALING JAYA, SELANGOR DARUL EHSAN

Keterangan : 5.1 - KERJA ICT

BIL	KETERANGAN	PRODUK	WARANT I	KUANTITI	UNIT	KADAR HARGA (RM)	JUMLAH (RM)
1	ICT Infrastructure Works						
	a. UTP Cabling						
	i. High Performance Category 6 UTP RJ-45 cable for 10/100 and 10/100/1000 Ethernet connections from stackable switch to network socket outlet similar to Krone or equivalent run in Galvanised Trunking/UPVC conduit.	Commscope or equivalent	25 years	66	NO		
	ii. UTP Cat 6 Patch cord 2 meter factory terminated.		1 year	93	NO		
	iii. UTP Cat 6 Patch Cord 3 Meters at Face plate side factory terminated.		1 year	39	NO		
	iv. Cat-6 UTP Patch Panel 24 Port		1 year	4	NO		
	v. Blank panel		1 year	4	NO		
	vi. Management ring		1 year	4	NO		
	vii. Rack 33U		1 year	1	NO		
	viii. Rack 42U		1 year	1	NO		
	b. Fiber Optic Cabling						
	1. Singlemode 6 core 9u/125um indoor fiber X 2						
	i. Server Room to Block A, Level 3 (150m)		1 year	150	m		
	2. Splicing c/w SC 9/125um and 50/125um pigtail, PVC, 1 mtr (SM/MM)		1 year	12	NO		
	3. Fiber Panel standart Connector (SC)		1 year	2	NO		
	4. Fiber Patch Cord (SC-LC) 3 METER SM		1 year	2	NO		
	c. Miscellaneous Items (Professional Services And Supporting Items)						
	i. To provide inspection, testing & comissioning, Hardware & Fitting, Durable labeling for both end utp cat 6		1 year	1	L/S		
	ii. To ensure all existing network equipment/ component/ cabling is functioning before and after project implementation		1 year	1	L/S		

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)

Tajuk Projek : KERJA MEMBAIKPULIH, MENAIKTARAF SERTA KERJA -KERJA YANG BERKAITAN DI BANGUNAN BLOK A UNTUK UNIVERSITI TEKNOLOGI MARA DI UiTM KAMPUS JALAN OTHMAN, PETALING JAYA, SELANGOR DARUL EHSAN

Keterangan : 5.1 - KERJA ICT

BIL	KETERANGAN	PRODUK	WARANT I	KUANTITI	UNIT	KADAR HARGA (RM)	JUMLAH (RM)
	iii. The comprehensive commissioning report must include the User Acceptance Test, Delivery Order with contract number for active equipment , WIFI heatmap and network diagram. The tenderer must also include other additional documents as proof if requested by UiTM.		1 year	1	L/S		
2	Wireless Access Point (9115Xi) with smartnet	Cisco	1 year	27	NO		
	a. That can be used with existing controller and eligible for Limited Lifetime Warranty (LLW), which include :-						
	i. Enterprise 802.11ax						
	ii. Power Injector (J6) : 10 unit						
3	Access Switch with smartnet and eligible for Limited Lifetime Warranty (LLW)						
	a. C9200-24P-4G-A 24 ports full PoE+, 370W with single primary power supply	Cisco	1 year	4	NO		
	b. SFP Transceiver module		1 year	8	NO		
JUMLAH (RM)							