

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)

Tajuk Projek : Kerja-Kerja Naiktaraf Gelanggang Tennis Serta Kerja -Kerja Berkaitan di Pusat Sukan UiTM Untuk Universiti Teknologi Mara (UiTM) Shah Alam

Keterangan : 2.1 - KERJA AWAM / ARKITEK

BIL	KETERANGAN	UNIT	HARGA (RM)
	BILL NO.2 : CIVIL WORKS		
	NEW WORKS		
	NOTE:		
	These works include supplying, installing, constructing and relating to the work completed perfectly in accordance with the specifications and drawings. All samples and colors of materials must be approved by the S.O. The contractor MUST submit the catalogue for the selection, together with the drawings and specifications provided.		
	All painting and coating work must be guaranteed against any defects in material and workmanship for a minimum period of 1 years or more by the Manufacturer and the work is carried out by a Specialist certified by the Manufacturer and must set the relevant Certificate or Letter of Declaration.		
	The Certificate of Warranty must be submitted before the Certificate of Practical Completion is issued by the UiTM S.O		
	All actual dimension & size need to be measured on site. (Approximate : 2664.48m ²)		
1	Surface Preparation Work Before Painting Works :		
1.1	Washing works until the entire surface is clean by using 'water jetting' pressurized water at a p.s.i rate that is suitable for entire court and other related surfaces such as drawings, specifications and approval by S.O. All surfaces to be painted must be dry and clean of dust, sand, grease, moss, mold, and any foreign matter; and any traces of peeling, chalk, oil, etc. Refer to drawing.	LS	
1.2	To repair the cracks on the court surface and effected stagnant water puddles area using SIKA cement mixture or equivalent to S.O approval. Refer to drawing.	LS	
2	Painting Works :		
2.1	Supply and plaster the finishing surface with textured material from BINA brand court surface DURACOURT or equivalent (MS 134: 2007 certification from SIRIM) come with manufacture guarantee which include of 1 layer of DURACOURT EMULSION or equivalent, 2 layer of DURACOURT MASTIC or equivalent and 2 layer of DURACOURT : DECO BLUE/ DECO GREEN/ DECO RED or equivalent to Arch's and S.O approval. Refer to drawing.	LS	
2.2	To prepare court lines using DURACOURT DECO WHITE or equivalent to Arch's and S.O approval. Refer to drawing.	LS	
3	OTHERS		
3.1	Any other works which are not mentioned above but necessary for completion and S.O. approval (tenderer must state below)		

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)



Tajuk Projek : Kerja-Kerja Naiktaraf Gelanggang Tennis Serta Kerja -Kerja Berkaitan di Pusat Sukan UiTM Untuk Universiti Teknologi Mara (UiTM) Shah Alam

Keterangan : 2.1 - KERJA AWAM / ARKITEK

BIL	KETERANGAN	UNIT	HARGA (RM)
	i)	LS	
	ii)	LS	
	iii)	LS	
JUMLAH (RM)			