

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)

Tajuk Projek : Cadangan Naiktaraf Dewan Kuliah 1 Dan Dewan Kuliah 2 Serta 3 Unit Ruang Parkir Berbumbung DI MASMED, UiTM Shah Alam, Selangor Darul Ehsan.

Keterangan : 5.1 - Kerja-Kerja ICT

BIL	KETERANGAN	PRODUK	WARANT I	KUANTITI	UNIT	KADAR HARGA (RM)	JUMLAH (RM)
1	ICT Infrastructure Works						
	a. UTP Cabling						
	i. High Performance Category 6 UTP RJ-45 cable for 10/100 and 10/100/1000 Ethernet connections from stackable switch to network socket outlet similar to Krone or equivalent run in Galvanised Trunking/UPVC conduit.	Commscope or equivalent	25 years	10	1		
	ii. UTP Cat 6 Patch cord 2 meter factory terminated.		1 year	12	1		
	iii. UTP Cat 6 Patch Cord 3 Meters at Face plate side factory terminated.		1 year	8	1		
	iv. Cat-6 UTP Patch Panel 24 Port		1 year	1	1		
	v. Blank panel		1 year	2	1		
	vi. Management ring		1 year	2	1		
	b. Miscellaneous Items (Professional Services And Supporting Items)		1 year	1	L/S		
	i. To provide inspection, testing & commissioning, Hardware & Fitting, Durable labeling for both end utp cat 6						
	ii. To ensure all existing network equipment/ component/ cabling is functioning before and after project implementation						
	iii. The comprehensive commissioning report must include the User Acceptance Test, Delivery Order with contract number for active equipment, WIFI heatmap and network diagram. The tenderer must also include other additional documents as proof if requested by UiTM.						
2	Wireless Access Point (9115Xi) with smartnet (1 year)	Cisco	1 year	1	1		
	a. That can be used with existing controller, which include :-						
	i. Enterprise 802.11ax						
	ii. Power Injector (J6)						
3	Access Switch						

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)



Tajuk Projek : Cadangan Naiktaraf Dewan Kuliah 1 Dan Dewan Kuliah 2 Serta 3 Unit Ruang Parkir Berbumbung DI MASMED, UiTM Shah Alam, Selangor Darul Ehsan.

Keterangan : 5.1 - Kerja-Kerja ICT

BIL	KETERANGAN	PRODUK	WARANT I	KUANTITI	UNIT	KADAR HARGA (RM)	JUMLAH (RM)
	a. C9200-24T-4G-L with smartnet (1 year) 24 port 10/100/1000 4SFP LAN	Cisco	1 year	1	1		
	b. 1000BASE-T SFP Tranceiver module.		1 year	2	1		
JUMLAH (RM)							