

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)

Tajuk Projek : PERKHIDMATAN PENYELENGGARAAN INFRASTRUKTUR SISTEM BEKALAN ELEKTRIK SERTA KERJA-KERJA BERKAITAN DI UiTM CAWANGAN PAHANG, PAHANG DARUL MAKMUR BAGI TEMPOH SATU (1) TAHUN

Keterangan : 2 - JADUAL KADAR HARGA AWAM

BIL	KETERANGAN	UNIT	HARGA (RM)
1	Building Painting		
1.1	External Wall Painting		
	Prepare wall surface for painting inclusive of brushing and cleaning of dust and apply one coat weather resistant and anti-fungus ICI Pentalite sealer and coats weather resistant and anti-fungus ICI emulsion paint as described to plastered wall with approved UiTM corporate colour.	M2	
1.2	Internal Wall Painting		
	Prepare wall surface for painting inclusive of brushing and cleaning of dust and apply one coat ICI Pentalite sealer and 2 coats ICI emulsion paints as described to plastered wall	M2	
1.3	Ceiling Painting		
	Prepare and apply one coat sealer and two coats ICI emulsion paint to ceiling	M2	
1.4	Floor Painting		
	Prepare and apply one epoxy primer and two epoxy non-slip deck paint green in colour as described on concrete surface.	M2	
2	UiTM Logo		
	To supply and fix UiTM logo including wording as described and specified with polycarbonate and stickers	NOS	
3	To stencil switchgear number measuring 4 inch on switchgear	LUMP SUM	
4	Chain link Fence		
4.1	To supply and install 2100mm PVC coated chain link fence with barded wire around the building as described.	M	
4.2	To rectify and make good damaged chain link fence	M	
5	To rectify and make good damaged perimeter drain	M	
6	Road Works		
	To trim, grade and level sub grade to required fall and chamber and compact. Supply and lay 50mm thick sand base and compact. Supply and lay 230mm thick crusher run road base in two equal layers and compact. Supply and lay 65mm thick asphalted macadam binder course and 40mm thick macadam binder wearing course all inclusive of prime and binder bitumen.	M2	
7	Mosquito Net		
7.1	To supply and install mosquito net with dimension 4mm x 4mm.	M	
8	To supply and place sand in trench complete with 25mm thick cement mortar	M3	

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)

Tajuk Projek : PERKHIDMATAN PENYELENGGARAAN INFRASTRUKTUR SISTEM BEKALAN ELEKTRIK SERTA KERJA-KERJA BERKAITAN DI UiTM CAWANGAN PAHANG, PAHANG DARUL MAKMUR BAGI TEMPOH SATU (1) TAHUN

Keterangan : 2 - JADUAL KADAR HARGA AWAM

BIL	KETERANGAN	UNIT	HARGA (RM)
9	To supply and install aluminium door for substations (2 leaf door)	NOS	
10	To supply and install aluminium door for substations (single leaf door)	NOS	
11	To supply and install aluminium louvered window for substation.	M2	
12	To supply and install door or louvered window aluminium frame for substation.	M2	
13	To rectified and make good substation roofing and rain water down pipe.	M2	
14	To supply and install transformer Guard	M2	
15	To supply and deliver Standard Alloy High Security Pad Lock for Substation	NOS	
	Bumbung Dek Logam		
16	Membekal dan memasang bumbung dek logam berombak untuk bumbung atau dinding termasuk semua peralatan tambahan dan hendaklah mematuhi sepenuhnya arahan pengilang (diukur mengikut luas yang ditutup sahaja)	M2	
17	Membuka dan membuang bumbung dek logam berombak	M2	
18	Membekal dan memasang perabung	M	
19	Lapisan Kalis Air (water proofing)		
	Kontraktor hendaklah menggunakan tenaga pekerja daripada pembekal semasa melakukan kerja-kerja pemasangan lapisan kalis air termasuk tempoh jaminan (Warranty period) dari pembekal.		
19.1	Pressure grouting - crack injection (rawatan rekahan)	NOZZLE	
19.2	Liquid water proofing untuk:		
b	Bumbung konkrit	M2	
c	Bumbung gentian	M2	
d	Bumbung metal decking	M2	
e	Expection joint	M2	
f	Lantai Tiles	M2	
g	Lantai simen / konkrit	M2	
h	Dinding bata	M2	
i	Dinding konkrit	M2	
19.3	Membrane water proofing	M2	
19.4	Lapisan kalis air berasaskan simen (cementitious)	M2	

MAKLUMAT SPESIFIKASI KERJA (SKOP TERPERINCI)



Tajuk Projek : PERKHIDMATAN PENYELENGGARAAN INFRASTRUKTUR SISTEM BEKALAN ELEKTRIK SERTA KERJA-KERJA BERKAITAN DI UiTM CAWANGAN PAHANG, PAHANG DARUL MAKMUR BAGI TEMPOH SATU (1) TAHUN

Keterangan : 2 - JADUAL KADAR HARGA AWAM

BIL	KETERANGAN	UNIT	HARGA (RM)
20	Mover/ Transport		
20.1	Skylift	NOS/DAY	
20.2	Backhoe	NOS/DAY	
JUMLAH (RM)			